



NOTES:

1. FOR LEGEND, ABBREVIATIONS, AND GENERAL NOTES, SEE DWG. E-1. FOR INSTALLATION DETAILS, SEE DWG. E-2 AND E-4. FOR WIRING DIAGRAMS, SEE DWGS. E-3 AND E-4.
2. REPLACE EXISTING STROBE WITH THE SHOWN CANDELA RATED STROBE, AND REWIRE AS SHOWN. EXISTING BACKBOX AND CONDUIT STUB CAN BE UTILIZED IF IT IS SIMILAR TO THE TYPICAL STROBE OR COMBINATION BOX. SEE INSTALLATION DETAIL "B" ON DWG. E-2.
3. ONLY AFTER INSTALLED STROBES ARE TESTED AND OPERATIONAL, SHALL CONTRACTOR REMOVE EXISTING STROBE IN THE PRESENCE OF THE ENGINEER. PATCH WALL TO MATCH EXISTING WALL FINISH.
4. SINCE FIRE ALARM CIRCUIT LENGTH IS CRITICAL, ROUTING AND INSTALLATION OF ALL FIRE ALARM CIRCUITS SHALL BE AS SHOWN ON DRAWING.
5. DISCONNECT AND ABANDON EXISTING STROBE CIRCUITS IN CEILING. TAPE ENDS OF ABANDONED CONDUCTORS AND TAG AS ABANDONED. THIS WORK SHALL BE DONE IN THE PRESENCE OF THE ENGINEER.

THE PORT AUTHORITY
OF NEW YORK AND
LIBERTY

ENGINEERING PROGRAM MANAGER
WORLD TRADE
CENTER
CHIEF ELECTRICAL ENGINEER

No. Date Revision Approved

ENGINEERING DEPARTMENT

WORLD
TRADE
CENTER

ELECTRICAL

Title
FIRE ALARM SYSTEM
DEVICE UPGRADE
PHASE III
5 WTC 3rd, 4th, 5th & 6th FLOORS

4th FLOOR
STROBE LAYOUT
INSTALLATION
AND REMOVAL
EAST PART PLAN

This drawing subject to conditions in Contract. All
inventions, ideas, designs and methods herein are
reserved to Port Authority and may not be used
without its written consent.

FELDSSTEIN APOSTLE A.S.
Designed by Drawn by Checked by

NOVEMBER 26, 1999
Date

WTC-861.573 E-04-4E
Contract Number Drawing Number

I HEREBY CERTIFY THAT THIS IS A TRUE AND
CORRECT COPY OF ONE OF THE CONTRACT
DRAWINGS CONSTITUTING A PART OF
CONTRACT NO. WTC-861.573 IN
THE FORM IN WHICH SAID DRAWINGS
EXISTED AT THE TIME THE SAID CONTRACT
WAS EXECUTED BY THE PARTIES.

DATE 2/1/00 CONTRACT ENGR./ARCH.

DATE 2/1/00 ENGINEERING PROGRAM MGR.

